



नगर कार्यपालिकाको कार्यालय

Office of the Municipal Executive



(Google Plus Code: C8RJ+C6 Neulapur)

सैनवार, बर्दिया
Sainawar, Bardia


लुम्बिनी प्रदेश, नेपाल
Lumbini Province, Nepal

मिति: २०८०/०२/२५

कोटेशन पेश गर्ने सम्बन्धी सूचना

(सूचना प्रकाशन मिति: २०८०/०२/२५)


प्रस्तुत बिषयमा यस ठाकुरबाबा नगरपालिका वडा नं. ०९ शिवपुर स्थित “ शिवपुर गाउँघर क्लिनिक निर्माण ” गर्नका लागि यसै सूचना साथ संलग्न राखिएको BOQ बमोजिमको कार्य के-कति दरेरेटमा गर्न सकिने हो ? तपसिल बमोजिमका कागजातहरु सहित मिति २०८०/०२/३२ गते कार्यालय समयभित्र नगरपालिकाको कार्यालयमा पेश गर्नुहुन यस नगरपालिकामा सूचिकृत भएका सम्पूर्ण निर्माण व्यवसायी/फर्महरुलाई सूचित गरिन्छ ।


२०८०/०२/०५
राजेश्वर रिजाल
प्रमुख प्रशासकीय अधिकृत

तपसिल:

१. रितपूर्वक भरिएको BOQ
२. कम्पनी दर्ताको प्रमाणपत्र
३. “घ” वर्ग निर्माण व्यवसायी इजाजतपत्रको प्रतिलिपि
४. स्थायी लेखा नम्बर (प्यान) दर्ता प्रमाणपत्रको प्रतिलिपि
५. आ.व २०७८/०७९ को करचुक्ता प्रमाणपत्रको प्रतिलिपि

Thakurbaba Municipality
Office of Municipal Executive
Sainawar Bardiya



Name of Project : Shivpur Gaughar Clinic Nirman

Location of Project: Thakurbaba Municipality-09

Types of works : Building Construction

Estimated Work Completion Date : 2080/05/20


F/Y:

2079/080

Budget Sub-Head No :

BOQ

A	General Works	Unit	Quantity	Rate(NRS)	Rate in Words	Amount(NRS)	Remarks
1	Supply and erection of hording board 1200x900 mm size including full compensation for labour,materials,transoprtation and other incidental all complete.[SS-110]	PS	1	2500.00	two thousand, five hundred	2,500.00	
B	Civil Works						
1	Back filling with approved sand (transported Sand from outside) in to the flooring of building/structure/ground. Back filling materials shall be applied on layers by layers of 150 mm thick, watering and compaction, all complete as per specification,drawings and as per Instruction of Site Engineer.	Cum	23.02			-	
2	Providing and laying of hand packStone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications and as per Instruction of Site Engineer.	Cum	4.13				
3	Providing, laying, compacting and curing plain cement concrete M10 (1:3:6) with 53 grade OPC cement, crusher Washed sand and crushed aggregate(using mixture machine) finishing to approved level, lines and dimensions using vibrator and all complete as per drawings, specifications and as per Instruction of Site Engineer.	Cum	4.82				


रामहरि रिजाल
प्रमुख प्रशासकीय अधिकारी

Name of Project : Shivpur Gaughar Clinic Nirman
 Location of Project: Thakurbaba Municipality-09
 Types of works : Building Construction
 Estimated Work Completion Date : 2080/05/20



F/Y: 2079/080
 Budget Sub-Head No :

A	General Works	Unit	Quantity	Rate(NRS)	Rate in Words	Amount(NRS)	Remarks
4	Formworks: Providing 19mm thick waterproof plywood and steel prop formwork for all concrete works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett for	Sqm	106.53				
5	Providing, laying, compacting and curing plain	Cum	14.02				
6	Reinforcement Steel Works: Providing, straightening, cleaning, cutting, fabricating, bending, stirrups making and tying TMT (Fe 500) for main reinforcement bars and binding the bars with 18 gauge annealed wire for tying them at each junction as per design	KG	1528.74				
7	Providing & laying with approved quality local chimney made first class bricks for super and substructure in 1:4 cement(OPC 53 grade) sand mortar finished in perfect line & level including wetting the bricks, packing the joints & curing the work all co	Cum	11.07				
8	Supplying and Plastering with 12.5 mm plaster in walls in 1:4 cement sand plaster in walls in perfect line and level using approved quality of OPC cement and sand include curing and all works complete and as per the instruction of the site Engineer.	Sqm	97.89				

Handwritten signature
 प्रमुख प्रशासकीय अधिकृत

Name of Project : Shivpur Gaughar Clinic Nirman
 Location of Project: Thakurbaba Municipality-09
 Types of works : Building Construction
 Estimated Work Completion Date : 2080/05/20



F/Y: 2079/080
 Budget Sub-Head No :

BOQ

A	General Works	Unit	Quantity	Rate(NRS)	Rate in Words	Amount(NRS)	Remarks
9	Supply and fixing of Seasoned Sal Wood Frame (75mmx100mm)for Door/Window/ Ventilation including one coat of Primer and two coat of Emael Painting with all hardware item (Holdfast etc)and all complete works per specification as per Instruction of Site Engineer.	Cum	0.30				
10	Supplying and fixing Readymade Door (1.7mx0.8m) Using GI Coloured sheet in salwood frame(75mmx80mm) with all hardware items(hings,chiskine,handle etc) including one coat primer and two coat enamel painting and all complete as per instruction of engineer	Ls	1.00				
11	Supply and fitting 12mm water proof ply wood for window Shutter all complete assoceries as per instruction of site Engineer	Sqm	9.00				
12	38mm thick Screeding Works(1:2:4) with 12mm round agreeagate with 3mm punning (1:1) at top finish	Sqm	57.54				
Sub- Total							
Vat(13%)							
General Works							
Grand Total							


Total Amount In Words :

Name Of The firm :

Authorized Signature & Stamp :

Designation :

Date:


 राजहरि रिजाल
 प्रमुख प्रशासकीय अधिकृत