



# नगर कार्यपालिकाको कार्यालय



## Office of the Municipal Executive

(Google Plus Code: C8RJ+C6 Neulapur)

सैनवार, बर्दिया  
Sainawat, Bardiya

लुम्बिनी प्रदेश, नेपाल  
Lumbini Province, Nepal

मिति २०८१/०१/२४

ने.सं.११४४ चौलागा त्रयोदशी २८ सोमबार


विषय: दरभाउपत्र (कोटेशन)पेश गर्ने सम्बन्धि सार्वजनिक सूचना ।

सूचना प्रकाशन मिति: २०८१ १०१ २४

प्रस्तुत विषयमा यस कार्यालयबाट वडा नं.१ को त्रिभुवन मा.वि. ठाकुरबाबा-०१ भुरिगाँउ मा शौचालय बनाउनु पर्ने भएकोले यस पत्रसाथ सम्लग्न BOQ बमोजिमको सामग्री के कति दररेटमा आपूर्ति तथा निर्माण गर्न सकिने हो मिति २०८१/०१/२८ गते भित्र दरभाउपत्र तपसिल बमोजिमको कागजातसहित पेश गर्नु हुन जानकारी गराइन्छ ।

तपसिल:

- १) व्यवसाय दर्ता प्रतिलिपि
- २) स्थाई लेखा नम्बर दर्ता प्रमाणको प्रतिलिपि
- ३) कर चुत्ता आ.व.२०७९/०८० प्रमाणपत्रको प्रतिलिपि
- ४) ठाकुरबाबा नगरपालिकामा फर्म सुचिकृत भएको प्रमाणपत्र वा नभएको भए सुचिकृत हुनका लागि निवेदन

  
राजेश्वर रिजाल  
प्रमुख प्रशासकीय अधिकृत

Thakurbaba Municipality  
Office of Municipal Executive  
Sainawa, Bardia



Project Name :- Toilet Construction in Tribhuwan School

Location :- Thakurbaba-01, Bhurigaun

Type of Work :- Building Construction

Estimated Work Completion Date :- 2081-03-15

Contract No :

F/Y: 2080/81

Budget Sub-Head  
No :

BOQ

SN.	Description	Unit	Quantity	Rates		Amount ( NRs)	Remarks
				Rate (Rs)	Rates in Word		
A.	General Work						
1	Supply and erection of Project Information board 1.8 x 1.2 m size including full compensation for labour, materials, transportation and other incidental all complete as per Instruction of site Engineer.	PS	1.00	3000.00		3000.00	
		Total Of General Cost				3000.00	
B.	CIVIL WORK						
1	Earthwork excavation in all Soft/Medium soils for building foundation and site development by Hydraulics Exavator, lift up to 1.5m, stacking of excavated materials at 10m, clear from the edge of foundation trench, all complete as per specification, drawings and instruction of site engineer	Cum	42.75				
2	Back filling(Manually) with Exavated Earth filling material to the flooring of building/structure/ground. Back filling materials shall be applied on layers by layers of 150 mm thick, watering and compaction, includes haulage distance of 10m and all complete as per specification, drawings and Instruction of Site Engineer.	Cum	34.20				
3	Filling with approved soil (transported soil from outside) in ground. Back Filling materials shall be applied to watering and all complete as per specification, drawings and Instruction of Site Engineer.	Cum	6.00				
4	Supplying And Laying Of Dry Brick Flooring in perfect line and level with Sand including Ground Compaction and the cost of all materials and other accessories etc all complete as per specification, drawings and Instruction of Site Engineer	Job	1.00				



SN.	Description	Unit	Quantity	Rates		Amount ( NRs)	Remarks
				Rate (RS)	Rates in Word		
5	Providing and laying compacting and curing Plain cement concrete (1:2:4) with cement, washed sand and crushed aggregate finishing to approved level, lines and dimensions all complete as per drawing specification and instruction of the site engineer.	Cum	2.15				
6	Providing laying compacting and curing 1:1.5:3 ( M20) reinforcement concrete for beam column work with cement water, washed sand and including Crushed well shaped aggregate material placing in position. vibrating, compacting, finishing, curing concrete of specified strength.	Cum	3.76				
7	Providing & laying with approved quality First class chimney brick masonry work in 1:4 cement sand mortar including full compensation for all labour, other incidentals required to complete the work.	Cum	10.52				
8	12.5mm thick cement washed sand plaster in 1:4 ratio on wall of good finish including racking the joint, wetting of surfaces & curing the work all complete.	Sqm	67.75				
9	Supplying and laying 38mm thick PCC in Flooring in the ratio of 1:2:4 with approved quality of OPC cement sand and 12 mm down aggregates including 1:1 C/S punning all works complete as per Instruction of Site Engineer.	Sqm	10.42				
10	3mm thick punning work cement(OPC)and water(1:1) as per Instruction of Site Engineer.	Sqm	9.81				
11	Centering and shuttering formwork with approved ply-bord/ metal sheet for all kinds of RCC .work including all necessary propping, scaffolding, staging, suporting dismantalling and clering from the site including shuttering all complete as per drawing ,specification.	Sqm	44.11				
12	Torsteel stell bars (Grade 415) or TMT reinforcement work including straightening, cleaning, cutting, bending with 20 SWG annealed wire & fixing in position as per drawing bar bending schedule for column ,beam. Work as per specification drawing.	Kg	1800.76				



Gumy

BOQ  
सुदूरपश्चिम प्रदेश, कैलाली जिल्ला, बर्दघाट  
(सं. २०३३)

SN.	Description	Unit	Quantity	Rates		Amount ( NRs)	Remarks
				Rate (Rs)	Rates in Word		
13	Providing and fixing of 26 guage (0.37 mm) Coloured corrugated CGI sheet (meadium class) for roof including fixing in proper shape and size with all necessary rails screws bolts and nuts washer J & L hooks etc including cost of materials and accessories etc all complete as per specification, drawings & Instruction of Site Engineer.	Sqm	29.06				
14	Supplying and Fitting of Different MS Section to make Roof truss Including One Coat Primer and Two Coat Enamail Paint with complete Installation In Position Line and Level As per Instruction of Site Engineer	Kg	502.75				
15	Providing and alying glazed ceramic tile of approved shape and size(12"*12") glazed wall tile kajaria, johnson .or equivalent)	Sqm	13.50				
16	Providing and alying 12mm thik non glazed the flooring work in 1:4 glazed floor tile (12"*12")kajaria, johnson .or equivalent)	Sqm	12.96				
17	Supplying and Fitting of Different MS Section to make metal door ventilation and water tank stand Including One Coat Primer and Two Coat Enamail Paint with complete Installation In Position Line and Level As per Instruction of Site Engineer	Kg	418.83				
19	Supplying and Fixing of concealed CPVC pipe and fitting in water Supply and PVC pipe in Waste Water discharge and In Septic Tanki ans Soak pit Inlet outlet with self design by contractor according to drawing from water Supply to Septic tank as per instruction of site engineer	Job	1.00				
20	Supply and fixing of 530 mm Porcelain clay white glaze Pan Hindwere shera or equivalent brand with complete set including all assories as per the instruction of site engineer.	Set	6.00				
21	Supply and fixing of (50x40)cm Porcelain clay white glaze Oval Wash basin Hindwere shera or equivalent brand with complete set including all assories as per the instruction of site engineer.	Set	2.00				
22	Supply and fixing of 500 Ltr. PVC\HDPE Water Tank including all assories and fitting as per the instruction of site engineer.	PS	1.00				





*Spung*

SN.	Description	Unit	Quantity	Rates		Amount ( NRs)	Remarks
				Rate (Rs)	Rates in Word		
23	Supply and fixing of Chrome Plate Soap Dish including all assories as per the instruction of site engineer.	No	2.00				
24	Supply and Fixing 4" PVC Floor Grating with matchable PVC Grating plate including all assories as per the instruction of site engineer.	No	6.00				
25	Supply of materials and wiring with PVC Insulated copper wire 2-1.5 Sq. mm in NS Approved PVC Pipe without any joint in middle of the span with necessary connecting, fixing, insulation and jointing of bends, circular & metal Junction boxes, six/four gang switch materials as per drawing and specification and as instruction of site engineer. a)Light/ Fan Points Light and Fan point	Points	8.00				
		Total Construction Cost					
		VAT(13%)					
		Total General Cost					
		GRAND TOTAL COST					