



नगर कार्यपालिकाको कार्यालय



Office of the Municipal Executive

(Google Plus Code: C8RJ+C6 Neulapur)

सैनवार, बर्दिया
Sainawar, Bardiya

लुम्बिनी प्रदेश, नेपाल
Lumbini Province, Nepal

मिति २०८१/०१/२४

ने.सं.११४४ चौलागा त्रयोदशी २८ सोमबार


विषय: दरभाउपत्र (कोटेशन)पेश गर्ने सम्बन्धि सार्वजनिक सूचना ।

सूचना प्रकाशन मिति: २०८१ १०१। २४

प्रस्तुत विषयमा यस कार्यालयबाट वडा नं.३ को सरस्वती आ.वि. ठाकुरबाबा-०३ नेउलापुर मा शौचालय बनाउनु पर्ने भएकोले यस पत्रसाथ सम्लग्न BOQ बमोजिमको सामग्री के कति दरेटमा आपूर्ति तथा निर्माण गर्न सकिने हो मिति २०८१/०१/२८ गते भित्र दरभाउपत्र तपसिल बमोजिमको कागजातसहित पेश गर्नु हुन जानकारी गराइन्छ ।


तपसिल:

- १) व्यवसाय दर्ता प्रतिलिपि
- २) स्थाई लेखा नम्बर दर्ता प्रमाणको प्रतिलिपि
- ३) कर चुत्ता आ.व. २०७९/०८० प्रमाणपत्रको प्रतिलिपि
- ४) ठाकुरबाबा नगरपालिकामा फर्म सुचिकृत भएको प्रमाणपत्र वा नभएको भए सुचिकृत हुनका लागि निवेदन


प्रमुख प्रशासकीय अधिकृत

Thakurbaba Municipality
Office of Municipal Executive
Sainnagar Bardiya

Signature



Project Name :- Toilet Construction in Swarwati Aa.Vi School Neulapur

Location :- Thakurbaba-03, Neulapur

Type of Work :- Toilet Construction

Estimated Work Completion Date :- 2081-03-15

Contract No :

F/Y: 2080/81

Budget Sub-Head No :


BOQ

Rates

SN.	Description	Unit	Quantity	Rate (Rs)	Rate in Words	Amount (NRs)	Remarks
A.	General Work						
1	Supply and erection of Project Information board 1.8 x 1.2 m size including full compensation for labour,materials,transoprtation and other incidental all complete as per Instruction of site Engineer.	PS	1.00	3000.00		3000.00	
	Total Of General Cost						
B.	CIVIL WORK						
1	Earthwork excavation in all Soft/Medium soils for building foundation and site development by Hydraulics Excavator, lift up to 1.5m, stacking of excavated materials at 10m, clear from the edge of foundation trench, all complete as per specification, drawings and instruction of site engineer	Cum	24.75				
2	Back filling(Manually) with Exavated Earth filling material to the flooring of building/structure/ground. Back filling materials shall be applied on layers by layers of 150 mm thick, watering and compaction, includes haulage distance of 10m and all complete as per specification,drawings and Instruction of Site Engineer.	Cum	19.80				
3	Filling with approved soil (transported soil from outside) in ground. Back Filling materials shall be applied to watering and all complete as per specification,drawings and Instruction of Site Engineer.	Cum	6.00				
4	Supplying And Laying Of Dry Brick Bat for Flooring in with Sand including Ground Compaction all complete in 13 SQM as per specification, drawings and Instruction of Site Engineer	Job	1.00				
5	Providing and laying compacting and curing Plain cement concrete (1:2:4) with cement, washed sand and crushed aggrete finishing to approved level, lines and dimensions all complete as per drawing specification and instruction of the site engineer.	Cum	0.95				

Thakurbaba Municipality
Office of Municipal Executive
Sainawar Bardiya

Sum



Project Name :- Toilet Construction In Swarwati Aa.Vi School Neulapur

Location :- Thakurbaba-03, Neulapur

Type of Work :- Toilet Construction

Estimated Work Completion Date :- 2081-03-15

Contract No :

FY:

2080/81


Budget Sub-Head No :

BOQ

Rates

SN.	Description	Unit	Quantity	Rate (Rs)	Rate in Words	Amount (NRs)	Remarks
6	Providing laying compacting and curing 1:1.5:3 (M20) reinforcement concrete for beam column work with cement water, washed sand and including Crushed well shaped aggregate material placing in position, vibrating, compacting, finishing, curing concrete of specified strength.	Cum	2.26				
7	Providing & laying with approved quality First class chimney brick masonry work in 1:4 cement sand mortar including full compensation for all labour, other incidentals required to complete the work.	Cum	6.91				
8	12.5mm thick cement washed sand plaster in 1:4 ratio on wall of good finish including racking the joint, wetting of surfaces & curing the work all complete.	Sqm	57.94				
9	Centering and shuttering formwork with approved ply-board/ metal sheet for all kinds of RCC work including all necessary propping, scaffolding, staging, supporting dismantling and clearing from the site including shuttering all complete as per drawing specification.	Sqm	32.11				
10	Torsteel steel bars (Grade 415) or TMT reinforcement work including straightening, cleaning, cutting, bending with 20 SWG annealed wire & fixing in position as per drawing bar bending schedule for column, beam. Work as per specification drawing.	Kg	1680.07				

Thakurbaba Municipality
Office of Municipal Executive
Sainawar Bardiya



Project Name :- Toilet Construction in Swartwati Aa.Vi School Neulapur

Location :- Thakurbaba-03, Neulapur

Type of Work :- Toilet Construction

Estimated Work Completion Date :- 2081-03-15

Contract No :

F/Y: 2080/81

Budget Sub-Head No :

BOQ

Rates

SN.	Description	Unit	Quantity	Rate (Rs)	Rate in Words	Amount (NRs)	Remarks
11	Providing and fixing of 26 guage (0.37 mm) Coloured corrugated CGI sheet (medium class) for roof including fixing in proper shape and size with all necessary rails screws bolts and nuts washer J & L hooks etc including cost of materials and accessories etc all complete as per specification, drawings & Instruction of Site Engineer.	Sqm	29.06				
12	Supplying and Fitting of Different MS Section to make Roof truss Including One Coat Primer and Two Coat Enamail Paint with complete Installation In Position Line and Level As per Instruction of Site Engineer	Kg	502.75				
13	Providing and alying glazed ceramic tile of approved shape and size (12"*12") glazed wall tile kajaria, johnson .or equivalent)	Sqm	13.50				
14	Providing and alying 12mm thik non glazed the flooring work in 1:4 glazed floor tile (12"*12")kajaria, johnson .or equivalent)	Sqm	12.96				
15	Supplying and Fitting of Different MS Section to make metal door ventilation and water tank stand Including One Coat Primer and Two Coat Enamail Paint with complete Installation In Position Line and Level As per Instruction of Site Engineer	Kg	418.83				
16	Supplying and Fixing of concealed CPVC pipe and fitting in water Supply and PVC pipe in Waste Water discharge and In Septic Tanki ans Soak pit Inlet outlet with self design by contractor according to drawing from water Supply to Septic tank as per instruction of site engineer	Job	1.00				

Thakurbaba Municipality
Office of Municipal Executive
Sainawar Bardiya


Project Name :- Toilet Construction in Swarnwati Aa.Vi School Neulapur

Location :- Thakurbaba-03, Neulapur

Type of Work :- Toilet Construction

Estimated Work Completion Date :- 2081-03-15

Contract No :



F/Y: 2080/81

Budget Sub-Head No :

BOQ

Rates

SN.	Description	Unit	Quantity	Rate (Rs)	Rate in Words	Amount (NRs)	Remarks
17	Supply and fixing of 530 mm Porcelain clay white glaze Pan Hindwere shera or equivalent brand with complete set including all assories as per the instruction of site engineer.	Set	6.00				
18	Supply and fixing of (50x40)cm Porcelain clay white glaze Oval Wash basin Hindwere shera or equivalent brand with complete set including all assories as per the instruction of site engineer.	Set	2.00				
19	Supply and fixing of 500 Ltr. PVC/HDPE Water Tank including all assories and fitting as per the instruction of site engineer.	PS	1.00				
20	Supply and fixing of Chrome Plate Soap Dish including all assories as per the instruction of site engineer.	No	2.00				
21	Supply and Fixing 4" PVC Floor Grating with matchable PVC Grating plate including all assories as per the instruction of site engineer.	No	6.00				
22	Supply of materials and wiring with PVC Insulated copper wire 2-1.5 Sq. mm in NS Approved PVC Pipe without any joint in middle of the span with necessary connecting, fixing, insulation and jointing of bends, circular & metal Junction boxes, six four gang switch materials as per drawing and specification and as instruction of site engineer. a) Light Fan Points Light and Fan point	Points	8.00				
				Total Construction Cost			
				VAT(13%)			
				Total General Cost			