

स्थायी लेखा नं.: २०१२९६१९०  
कार्यालय कोड नं.: ८०१०५१२८

ठाकुरबाबा नगरपालिका  
Thakurbaba Municipality



# नगर कार्यपालिकाको कार्यालय

## Office of the Municipal Executive

(Google Plus Code: C8RJ+C6 Neulapur)

सैनवी बजार  
Sainawar, Bardiya

लुम्बिनी प्रदेश, नेपाल  
Lumbini Province, Nepal



विषय: दरभाउपत्र पेश गर्ने सम्बन्धि सार्वजनिक सूचना ।

(सूचना प्रकासन मिति: २०८३/०२/१९)

प्रस्तुत विषयमा यस कार्यालयबाट वडा न. ०६ मा जनज्योति मा.बि. बकुवा मा रहेको अधुरो सरस्वती मन्दिर निर्माण कार्य सम्पन्न गर्नुपर्ने भएकोले उक्त कार्यको स्वीकृत लागत अनुमान रु.२७०,४०८.०७ (मु.अ.क.सहित) भित्र रही कार्यालयबाट उपलब्ध गराइएको BOQ तथा Specification बमोजिम उक्त निर्माण कार्य गर्न ईच्छुक निर्माण ब्यवसायी तथा फर्महरुबाट यो सूचना प्रकाशित भएको मिति देखि ३ दिन भित्र (मिति २०८३/०२/२२) भित्र के/कति दरमा गर्न सकिने हो? दरभाउपत्र र तपसिल बमोजिमको कागजातसहित पेश गर्नु हुन जानकारी गराइन्छ ।

तपसिल:

- १) व्यवसाय दर्ता प्रतिलिपि.
- २) स्थाई लेखा नम्बर दर्ता प्रमाणको प्रतिलिपि
- ३) अ. बा २०८१/८२ को कर चुत्ता प्रमाणपत्रको प्रतिलिपि

मंगल बहादुर शाही  
प्रमुख प्रशासकीय अधिकृत

"समुन्नत ठाकुरबाबा: सबल नगरवासी"

वेबसाइट: www.thakurbabamun.gov.np ईमेल: thakurbabamun@gmail.com



Thakurbaba Municipality  
Office of Municipal Executive  
Sainawar Bardiya  
Bill Of Quantity

મંગલ બહાદુર શાહી  
સુખ પ્રશાસકીય અધિકૃત

Project Name :- Janajyoti maa.bi. Saraswati mandir nirman  
Location :- Thakurbaba-06,Bakuwa  
Type of Work :- mandir sudhar  
Estimated Work Completion Date : 2083/02/18

F/Y: 2082/083  
Budget Sub-Head No: 09

SN.	Description	Unit	Quantity	Rate In Figure	Rate In Words	Amount ( NRs)	Remarks
1	Providing & laying with approved quality local chimney made first class bricks for super and substructure in 1:4 cement(OPC 43 grade Minimum) sand mortar finished in perfect line & level including wetting the bricks, packing the joints & curing the work all complete as per drawings, specification & Instruction of Site Engineer.	CUM	2.74				
2	Supplying and Plastering with 12.5 mm plaster in walls in 1:4 cement sand plaster in walls in perfect line and level using approved quality of OPC cement and sand include curing and and all complete as per specification, drawings and Instruction of Site Engineer	SQM	11.08				
3	Supplying of black pipe/ms angle ready made truss including fitting and all complete as per specification, drawings and Instruction of Site Engineer	KG	42.48				
4	Supplying and Fitting of Different MS Section to make Grill Including One Coat Primer and Two Coat Enamail Paint with complete Installation In Position Line and Level and all complete as per specification, drawings and Instruction of Site Engineer	KG	78.00				
5	Providing and fixing of 26 guage (0.37 mm) Coloured corrugated CGI sheet (meadium class) for roof including fixing in proper shape and size with all necessary rails screws bolts and nuts washer J & L hooks etc including cost of materials and accessories etc all complete as per specification, drawings & Instruction of Site Engineer.	SQM	91.44				
6	Providing and fixing of 26 guage (0.37mm) colour GI sheet (medium class) for roof ridge of width 60 cm including fixing in proper shape and size with all necessary rails screws bolts and nuts washer J & L hooks etc including cost of materials and accessories etc all complete as per specification, drawings & instruction of Site Engineer	RM	16.00				
7	Supplying and laying of Porcelain Non Glazed tile on floor in perfect line and level of approved brand: kajaria, somany, nitco or equivalent in cement sand mortar C/M (1:4) of good finish including grouting joints, cost of all materials and accessories all complete as per specification , drawings and as Per Instruction of Site Engineer.	SQM	20.812				



मंगल बहादुर शाही  
प्रमुख प्रशासकीय अधिकृत

Thakurbaba Municipality  
Office of Municipal Executive  
Sainawar Bardiya  
Bill Of Quantity

Name :- Janajyoti maa.bi. Saraswati mandir nirman  
Location :- Thakurbaba-06.Bakuwa  
Type of Work :- mandir sudhar  
Estimated Work Completion Date : 2083/02/18

F/Y: 2082/083  
Budget Sub-Head No: 09 .

SN.	Description	Unit	Quantity	Rate In Figure	Rate In Words	Amount ( NRs)	Remarks
8	Providing and applying two coat of Interior Side Plastic Emulsion paint over one coat of primer on Wall Surface including brushing ,cleaning the surface with required materials and accessories, all complete as per specification ,drawings and Instruction of Engineer (approved Plastic Emulsion Paint)	SQM	48.31				
				TOTAL COST			
				VAT(13%)			
				GRAND TOTAL COST WITH VAT			

Grand Total In Words :

Name Of Firm:  
Name Of Proprieter :  
Firm Address :  
Authorize Signature and Stamp :  
Date :